



- NOTES:**
- Height above finished floor to top of trackway :- Approx 7550mm (to be as high as possible).
  - All steelwork to be painted WHITE.
  - Floor finish in Sports Hall :- 50mm Thick Junckers sprung timber floor (UNDERFLOOR HEATING).
- LEGEND:**
- Indicates 3no Main 'I' section steel roof beams.
  - Indicates 3no PFC's (by others) which suspend Continental trackway brackets & inserts.
- ALSO TO BE INSTALLED:**
- 1pr - 5-a-side wall anchors (fitted central in end walls).
  - 2no - Gamespost anchors to suit club model volleyball posts.
- (Note: 2no Ø95mm bushing covers to be installed by flooring contractor relative to volleyball lines as per diag CM-07).

LAYOUT PLAN OF SPORTS HALL

DISCUSSIONS ONLY